SPECIFICATION

OIL IMMERSED TRANSFORMER

1250 kVA 3Ph 50Hz

22000 – 400/230 V

TRANSFORMER TECHNICAL SPECIFICATION

1. SPEC No. T1250200509
2. CUSTOMER :
3. REQUIREMENT :

Quantity	Description			
	kVA	Phase	Hz.	Voltage
	1250	**3**	**50**	**22000 – 400/230**

4. SCOPE :

This specification covers oil immersed transformer

[X]	Core type	[X]	Natural self - cooled
[ ]	Shell type	[ ]	Forced - air - cooled
		[ ]	Forced - oil - forced - air cooled

The transformer will be designed suitable for used

[X]	Outdoor installation	[ ]	With cable end box
[ ]	Indoor installation	[X]	Without cable end box

On the system voltage

[ ]	3.3 kV.	[ ]	12 kV.		
[ ]	6.6 kV.	[X]	22 kV.		
[ ]	11 kV.	[ ]	24 kV.	[ ]	33 kV.

5. STANDARD :

The transformer , all equipment and materials shall be manufactured and tested in accordance with the latest applicable standard specifications and codes in the following list :

[ ]	ANSI	American Nation Standards Institute Incorporated (ANSI.C57.12)
[ ]	IEEE	Institute of Electrical and Electronic Engineers
[ ]	NEMA	National Electrical Manufacture's Association
[ ]	ASTM	American Society of Testing Materials
[ ]	VDE	Regulation and DIN Standard (VDE 0532/11)
[ ]	IEC	International Electrotechnical Commission (Publication 60076-1 to 60076-5)
[ ]	BSI	British Standard Institution (BS 171-1 to 171-5)
[X]	TIS.384-2525	

6. SERVICE CONDITION

The transformer and accessories shall be designed and constructed for installation the following conditions :

Altitude : up to 1000 M above sea level

Ambient : air temperature 40° C maximum

35° C average on one day

7. RATING

High Voltage Tension : **22000** V

Low Voltage Tension : **400/230** V

Tapping : Range [ ] -4x2.5% [X] ± 2x2.5%

Winding [X] HV winding [ ] LV winding

Location [ ] Adjusted inside the transformer tank

[X] Adjusted outside the transformer tank

[X] On the top of the transformer cover.

[ ] On the side of the transformer tank

HT and LT Bushing : Accordance with [X] DIN 42530,42531,42539

Mounted [X] On the top of the transformer cover

[ ] On the side of the transformer tank

[ ] Inside the cable box

Vector Group of Polarity : **Dyn11**

Frequency : 50 Hz.

Operation duty : Continuous Operation (DB)

Neutral point of the star winding will be designed for

[X] 100% accessible loading

[ ] 50% accessible loading

8. LOSS AND IMPEDANCE VOLTAGE :

The guaranteed losses and impedance voltage of the offered transformer shall comply with the figures in the table below :

Rating kVA	Watt loss		Percent Impedance Voltage at 75° C
	No load loss	Load loss at 75° C	
1250	**1800**	**16400**	**6**

9. TRANSFORMER CONSTRUCTION

Tank Each transformer shall be provided with a steel case of substantial construction , which shall be oil-tight and gas tight. The tank shall be capable of withstanding , without leakage or permanent distortion , a pressure of+5 p.s.i and shall withstand continuously a vacuum of 5 p.s.i inside of the tank. The tank cover shall be provided with suitable hand holes , if required. A grounding pad shall be provided on the tank wall near the base.

Core Core shall be constructed of high quality , nonaging , high permeability silicon steel and designed to accessible loading 110% rated voltage without making injury to the transformer core. The steel shall be in thin laminations , annealed after cutting and rolled to insure smooth surface at the edges. Both sides of each sheet shall be insulated with a durable , heat resistant baked enamel or varnish. The cores shall be rigidly clamped with positive locking devices to insure adequate mechanical strength to support the windings and reduce vibration to a minimum during operation.

Windings The design , construction and treatment of winding shall give proper consideration to all service factor , such as high dielectric and mechanical strength of insulation coil characteristic , uniform electrostatic flux distribution prevention of corona formation , and minimum restriction to free oil circulation. For transformer 1000 kVA and above the completed assembly of core and coil shall be tighted rigidly with the pressure ring made injury and shall be dried in a vacuum sufficient to insure elimination of air and moisture within the insulating structure. After the drying , process , assemble shall be immediately impregnated with dry oil.

Insulation class of winding as below :

Terminal	Insulation class (kV)	Low frequency test (kV)	BIL (kV)
HV.	**24**	**50**	**125**
LV.	**-**	**3.0**	**-**
Neutral	**-**	**3.0**	**-**

The insulation resistance between winding and earth tested by Meggar ohm. Meter not less than 2500 Vdc

P-E not less than	**1000**	M ohm.
S-E not less than	**1000**	M ohm.
P-S not less than	**1000**	M ohm.

At the ambient temperature 32° C and relative humidity 80%

Bushing The bushing shall conform and be located to the requirement of the reference standard.

Basic impulse insulation level (BIL) for bushings :

HV.	**125**	kV
HV. Neutral	-	kV
LV.	**30**	kV
LV. Neutral	**30**	kV

Transformer oil The transformer oil shall be will filtered and the dielectric strength before filling in transformer tank is not less than 30 kV / 2.5 mm. gap as tested by the method specified by ASTM D877 ,IEC 156. The dielectric strength of the sample of insulating oil taken from a new transformer shall not be less than 27 kV : when measured in accordance with ANSI Standard Method of testing Electrical Insulating Oil C59.2-1966 or equal.

Terminal Arrangement H.T. and L.T. bushings shall be equipped with solderless pad type connectors for AL. And CU. Conductor size as follow :

Terminal	Transformer Rating kVA	Applicable to AL. and Cu. Conductors		Number of Circuits
		Size (mm^2)	diameter (mm)	
HV.	**1250**	**35 – 95**	**7.5 – 16.0**	**1**
LV.		**185 – 400**	**17.6 – 25.6**	**4**
Neutral		**185 – 400**	**17.6 – 25.6**	**4**

Tank cleaning and Painting All surfaces shall be thoroughly cleaned by chemical. Interior surface shall be finished with oil - resisting point. Exterior surface shall be painted with a primer coat and two (2) finish weather – resisting coats , Gray gloss Enamel Tys NC – G001

10. TEMPERATURE :

Average winding temperature rise by resistance method when carrying max. continuous rated capacity : 65° C

Average top oil Continuous rated capacity : 60 ° C

Hottest spot winding temperature rise when carrying max. continuous rated capacity : 80° C

11. ACCESSORIES :

The transformer shall equipped with the following accessories :

X	Oil drain , filter press sampling valve.
X	Liquid level gauge
X	Upper filter press connection
X	Off-load tap changer
X	Lifting lugs.
X	Tank grounding provision.
X	Name plate.
	Oil thermometer.
	Dehydrating breather
	Buchholz relay
X	Mechanical Pressure relief device

Other standard accessories as per enclosed drawing.

12. TEST :

Each transformer shall be given the following test inaccordance with the reference standard.

a. Applied potential test.

b. Induced potential test.

c. Exciting current at rated voltage

d. No-load loss at rated voltage.

e. Full - load copper loss at rated current.

f. polarity check.

g. Impedance.

h. Temperature rise , if required.

We shall furnish four certified copies of test reports showing all the above tests at our expenses.



LIST OF PART		
No.	PART NAME	Qty
1.	Thermometer pocket	1
2.	Lifting eye for cover	2
3.	HV.Bushing with terminal connectors	3
4.	Off load tap changer	1
5.	LV.Bushing with terminal connectors	4
6.	Pressure relief device	1
7.	Bird Guard cap	3
8.	Oil filling pipe	1
9.	Liquid level gauge	1
10.	Surge arrester	3
11.	Bracket for surge arrester	3
12.	Nameplate with connection diagram	1
13.	Manufacturer plate	1
14.	Corrugated fins	4
15.	Tank	1
16.	Oil drain valve	1
17.	Sub base	2
18.	Earth terminal	1





Note : Surge arrester, line lead and ground lead, supplied by PEA

PRELIMINARY DRAWING : This drawing is for estimate only,showing approximate dimensions. It should not be referred to as the final drawing.

SEC SAHABHANT ELECTRIC CO.,LTD.

Project :

Tilte :

OUTLINE DRAWING
OIL IMMERSED TRANSFORMER
1250 kVA 3Ph 50Hz 22000 - 400/230 V.

Dimension in millimeters			Weight	Oil
H	L	W	kgs	Litres
1620	1710	1160	3010	730

Scale :

	Signature	Date
Drawn By		12/2/13
Checked By		12/2/13
Approved By		12/2/13

Requisition No.	Spec. No.	Drawing No.
		T1250200508